Florida

SMACNA Inc.

Quarterly Edition - January 2009

Volume 32

TECH/SPEC


NEWS

RENOVATIONS TO ROBERT E. LEE ELEMENTARY SCHOOL ORLANDO, FL



SHEET METAL CONTRACTOR: MCDONALD AIR & SHEET METAL, INC., ORLANDO, FL

RENOVATIONS TO ROBERT E. LEE ELEMENTARY SCHOOL ORLANDO, FL



Architect: C.T. Hsu & Associates, P.A., Orlando, FL

Roger Pafford, Lead Architect

Engineer: S.G.M. Engineering, Inc., Orlando, FL **General Contractor:** Clark Construction, Orlando, FL

Kory Kruel

Mechanical Contractor: W. Soule Company, Orlando, FL

Aaron Jones and R.C. Reeves

Mechanical Superintendents

Sheet Metal Contractor: McDonald Air & Sheet Metal, Inc., Orlando, FL

Jim Sheer, Project Manager

Ron Turmenne, Sheet Metal Superintendent

John Crown, Jobsite Foreman

The scope of the project involved the renovation of existing structures and adding some new areas that tie to existing structures. The \$600,000 sheet metal job required 60,000 lbs. of ductwork which included 3000 lbs. of spiral, 48,000 lbs. of rectangular duct, 5000 feet of snap lock pipe, and a stainless steel kitchen hood exhaust. In addition, two air conditioners at 150 tons each, 14 AHU's, and 23 exhaust fans were provided.

Challenges to the project were the necessity to carry on work while school was in session. The coordination of the work during school hours, required safety and badging to become a top priority. There was very little parking and access to the facility so Clark Construction, the general contractor, coordinated all phases of the work as closely as possible. Due to space limitations, material was off loaded in the staging areas of the work.

The entire sheet metal project, originally planned for two years-August, 2007 to March, 2009, will be completed six months ahead of schedule. Building No.1, the final building, was started on November 8, 2008.

Jim Sheer, McDonald Air and Sheet Metal, Inc. Project Manager stated: "For a renovation project, the job was coordinated very well by all trades."

MIAMI INTERMODAL CENTER (MIC) RENTAL CAR FACILITY MIAMI, FL



Sheet Metal Contractor: Lewis and Lambert, LLLP., Fort Worth, TX

The Miami Intermodal Center (MIC) Rental Car Facility will house all the surrounding rental car agencies and their vehicles in one building of over 4.3 million square feet. The project requires over 1.1 million pounds of sheet metal duct and 120 fans mostly to remove vehicle exhaust fumes from within 6 inches of the floor.

A unique aspect of the project is that many fuel dispensers are installed above grade level (this had never been done before). In order to draw off any fumes that may accumulate, there are 14 inch round spiral ducts installed on either side of the fuel dispensers to within 1 inch above the finished floor. The West end of the building on all three floors holds fuel dispensers and carwashes that wash a car in 25 seconds. The customer service area is on the fourth floor, so the arriving busses will bring customers up a long ramp to be dropped off on the roof.



MIAMI INTERMODAL CENTER (MIC) RENTAL CAR FACILITY MIAMI, FL



One challenge to the coordination of the project was the fact that no floor, where cars are driven, is level. In most areas, the floor slopes 14 inches over 60 feet and the floor above does not always pitch in the same direction. This made coordinating the ductwork to fit inside the allotted space tedious, as there is a 10 foot above finish floor clearance requirement for emergency vehicles. Many of the beams were 5.5 feet deep, with most of the duct 80 x 36 inches.

Once completed the MIC will be joined by a Bridge to the TRI-RAIL station to the East and a people mover is proposed on the West side to connect to the Miami International Airport.

Lewis and Lambert have been in business over 35 years. The company has experience in HVAC component fabrication, HVAC contracting and HVAC design. It has three operating divisions, the Spiral duct division, the Industrial division and an HVAC/sheet metal contracting division in Fort Worth, Texas. MFH of North Miami assisted in the fabrication of the rectangular duct in order to defray shipping expenses.



RAYTHEON TECHNICAL SERVICES COMPANY LLC., ORLANDO, FL



General Contractor: Pertree Construction, Inc., Orlando, FL **Sheet Metal Contractor:** Vickers Metal Works, Inc., Orlando, FL

The scope of the project called for Vickers Metal Works, Inc. to fabricate and install decorative wall cladding of .040 and .050 clear anodized aluminum inside the main lobby of the Raytheon Building in Orlando, Florida.

Custom panels were roll formed as required to fit the 17'-0" radius wall on each side of the existing water feature. Each panel was formed with 1/2" 90 degree returns on all edges. Reveals were 1/2" deep x 1 1/2" wide. Panels were adhered directly to plywood substrate using adhesive as required. Dimensions for each side were approximately 4' wide by 12' tall.

Custom panels were also formed to fit three sides and the base of two planters. Each planter was approximately 2' tall x 20' overall length.

The logo was fabricated using 1/2" PVC with brushed aluminum laminate installed by Vickers Metal Works, Inc.

The project required 80 hours for fabrication with field installation taking 130 hours.





FLORIDA SMACNA, INC. MEMBER FIRMS

In the sheet metal and air conditioning business, nobody knows excellence quite the way SMACNA Contractors do. After all, they wrote the book on it. Why take a chance on doing business with anyone who offers less.

Air Management Systems, Inc.

3801 Commerce Pkwy. Miramar, FL 33025 305-651-0440 Chris Hightower

All Southern Fabricators, Inc.

5010 126th Avenue N. Clearwater, FL 33760 727-573-4846 Manuel Santana, Jr.

Anderson Technical Systems, Inc.

333 W. Marion Avenue Edgewater, FL 32131 386-423-2500 Tim Anderson

Bohnert Sheet Metal

2225 NW 76th Street Miami, FL 33147 305-696-6851

William H. Marvel, Jr. (Skip)

BSA Sheet Metal

2530 Ali Baba Avenue Opa Locka, FL 33054 305-681-3771 John Rudisill

CADVANTAGE Drafting

Service, Inc. 2220 1st Avenue S. St. Petersburg, FL 33713 727-321-2072

Dan Sinclair

Cailis Mechanical Corp. 12555 Orange Drive, Suite 108

Davie, FL 33330 954-252-0263 **Emanuel Cailis**

Dodec Inc.

3140 W. 84th Street, Bay #2 Hialeah, FL 33018 305-826-4022 Trevor Pantry

EMC2 Sheet Metal Corp.

7537 N.W. 70th Street Miami, FL33166 305-885-9911 Javier Estrada

Ferber Sheet Metal Works, Inc.

P.O. Box 26069

Jacksonville, FL 32226-6069

904-356-3042 George Ferber

Lapin Sheet Metal Company

3825 Gardenia Avenue Orlando, FL 32839 407-423-9897 Ronald J. Lapin

Lee's Sheet Metal Works, Inc.

P.O. Box 756 East Palatka, FL 32131 386-328-5563 James Lee

McDonald Air and Sheet Metal, Inc. Sheet Metal Experts, Inc.

2730 Eunice Avenue Orlando, FL 32808 407-295-0220 Ralph Carver

Magnum Sheet Metal, Inc.

7470 NW 68th Street Miami, FL 33166 305-885-5656

William H. Murphy, Sr.

MetalFab, Inc. 28212 Rice Road San Antonio, FL 33576

352-588-9901 Wally Ruda

Moffitt Mechanical, LLC

1351 13th Avenue South, Suite 130 Jacksonville Beach, FL 32250 904-241-9944

John Moffitt

National Sheet Metal Co.

8318 Atlantic Blvd. Jacksonville, FL 32211 904-724-7476 Ed Dickey

Omega Test and Balance

126 Wisteria Avenue Fort Pierce, FL 34982 772-216-7362

Hugh Grimes

R. Neth & Son, Inc. 360 E. Landstreet Road Orlando, FL 32824 407-855-9096

Steven Woodley

Ray's Metal Works, Inc.

P.O. Box 700 Alachua, FL 32615 386-462-1415 Ray Burnsed, Sr.

8986 N.W. 105th Way Medley, FL 33178 305-805-2019 William F. Medlin

South Florida Sheet Metal

5217 NE Shore Village Terrace Stuart, FL 34996 954-647-6457

Wayne Bozer

United Sheet Metal Company

14945 NW 25th Court Miami, FL 33054 305-685-3526 Rich Applegate

Vickers Metal Works, Inc.

6701 Edgewater Commerce Pkwy.

Orlando, FL 32810 407-297-7546 Tim Vickers

OTHER CONTRIBUTORS TO THE FLORIDA SHEET METAL INDUSTRY

Advanced Metal Works All Ready Chute, Inc. **Apollo Construction & Engineering Colbert Air Conditioning Conquest Mechanical Crown Corr Erection D&J Sheet Metal DKG & Associates**

Day and Zimmerman

Digital Climate & Control **Energy Services Ins. Inc.** Florida Metal Art

FCR Mechanical Contractors

Industrial Steel JV Installation Lindab, Inc.

MFH Sheet Metal Fabricators, Corp.

Quality Metal Works, Inc.

Ray Williams Sheet Metal SDB Engineers and Constructors, Inc. **Superior Mechanical System Tech Services** TankServ, Inc.

Triple M Roofing Corp. **Union Air Conditioning Universal Fabrication Services**

skarr@flsmacna.org

NEW EDITION OF "ACCEPTED INDUSTRY PRACTICE FOR INDUSTRIAL DUCT CONSTRUCTION," 2ND EDITION

The second edition of SMACNA's "Accepted Industry Practice for Industrial Duct Construction" is a compilation of the latest accepted industry practices and construction techniques, having received wide acceptance for the fabrication and installation of industrial duct systems.

The 208 page guide covers round (long-seam and spiral) duct from 4 inches to 60 inch diameter, both reinforced or unreinforced, for operation

from 4 inch to 20 inch wg positive or negative pressure, and from ambient to 650 degrees F for carbon or stainless steel, 400 degrees F for galvanized steel, and 120 degrees F for aluminum.

Also included is information on rectangular duct fabricated from panels from a few inches up to 5 feet wide; all welded, Pittsburgh, grooved seam pipe lock or standing seam joined duct for operation from 4 inch to 20 inch wg positive or negative pressure and for the same

materials and temperature limits as round duct. Chapters on industrial applications, material properties, hangers and supports, fittings, vents, doors, discharge ducts (small stacks) and surface preparation of metals are part of this comprehensive publication.

Architects and engineers may purchase the publication at the discounted price of \$96 for the book, \$115 for the CD, and \$96 for the PDF download.

To order, contact Florida SMACNA, Inc. 321-242-8223.

Florida

SMACNA

• SMACNA'S CONSTRUCTION • SMACNA/ASHRAE S

- Accepted Industry Practices for Sheet Metal Lagging.
- Architectural Sheet Metal Inspection Guide.

STANDARDS

- Architectural Sheet Metal Manual, CADD Version 2.0
- Fire Smoke and Radiation Damper Installation Guide for HVAC Systems.
- Guide for Steel Stack Construction.
- Guidelines for Roof Mounted Outdoor Air-Conditioner Installations.
- HVAC Duct Systems Inspection Guide.
- Kitchen Ventilation Systems & Food Service Equipment Fabrication & Installation Guidelines.
- Residential Sheet Metal Guidelines.
- Seismic Restraint Manual: Guidelines for Mechanical Systems.
- Sheet Metal Welding Guide.

- SMACNA/ASHRAE Seismic Restraint Applications CD-ROM.
- Standard Practice in Sheet Metal Work.

• SMACNA'S DESIGN GUIDES

- Duct System Calculator Imperial.
- Ducted Electric Heat Guide for Air Handling Systems.
- Guidelines for Change Orders
- HVAC Systems Duct Design.

• SMACNA'S DUCT STANDARDS

- Accepted Industry Practice for Industrial Duct Construction.
- Fibrous Glass Duct Construction Standards.
- HVAC Air Duct Leakage Test Manual.
- HVAC Duct Construction Standards - Metal and Flexible.
- Rectangular Industrial Duct Construction Standards.
- Residential Comfort System Installation Standards Manual.
- Round Industrial Duct Construction Standards.

• Round Industrial Duct Construction Standards (RIDCS) Software Version 2.0.

Inc.

- Thermoplastic Duct (PVC) Construction Manual.
- Thermoset FRP Duct Construction Manual.

• SMACNA'S ENVIRONMENTAL PUBLICATIONS

- Building Systems Analysis and Retrofit Manual.
- Energy Systems Analysis and Management.
- HVAC Systems Applications.
- HVAC Systems Commissioning Manual.
- HVAC Systems Testing, Adjusting & Balancing.
- IAQ Guidelines for Occupied Buildings Under Construction.
- Indoor Air Quality A Systems Approach.
- TAB Procedural Guide.

Florida



6767 N. Wickham Road, Suite 400 Melbourne, Florida 32940



Florida SMACNA, Inc.

6767 N. Wickham Rd. #400 Melbourne, FL 32940

Tel: 321-242-8223 Fax: 321-242-8277

skarr@flsmacna.org

Susan E. Karr, CAE

Executive Vice President

http://www.flsmacna.org